

THE FOLLOWING MINIMUM BACKFLOW PREVENTION/ENCLOSURE NOTES
SHOULD APPEAR ON PLANS WHERE APPLICABLE

1. ENCLOSURE TYPE MUST BE (HOTBOX, HYDROWCOWL OR NATIONAL PRODUCTS (AIRE SYSTEMS), LIST ONE)
2. ENCLOSURE OUTSIDE DIMENSIONS ARE (____)WIDE,(____)DEEP & (____) HIGH
3. HEATER(S) SHALL BE (__) UNIT(S),(_____)WATTS, 120 VAC, 1 PHASE, 20 AMPS. HEATERS FOR ABOVE GROUND ENCLOSURES MUST BE OF THE TYPE AND SIZE RECOMMENDED AND APPROVED BY THE MANUFACTURER. HEATER UNITS COME WITH THE “HOTBOX” ENCLOSURE, BUT ARE ORDERED SEPARATELY FOR THE “HYDROCOWL” ENCLOSURES.
4. ELECTRICAL OUTLET(S) SHALL BE TYPICAL FOR OUTDOOR USE AND INSTALLED ON A GROUND FAULTED CIRCUIT. THE OUTLET SHALL BE MOUNTED A MINIMUM OF 6" ABOVE THE HIGHEST FLANGE FACE.
5. FOUNDATION SHALL BE A 6" CONCRETE PAD THAT IS (__”) WIDE AND (__”) LONG. ASSEMBLY ENCLOSURES SHALL BE AFFIXED TO A CONCRETE SLAB OF 3,000 PSI MIX CONCRETE AND (1) LAYER OF WELDED WIRE MESH. SLAB SHALL BE PITCHED TO DRAIN AT A SLOPE OF 1% TOWARDS DRAIN PORT END OF ENCLOSURE. PAD MUST BE FINISHED SO ENCLOSURE SETS FLUSH WITH PAD SURFACE WITH NO GAPS. ENCLOSURE SHALL BE CENTERED ON PAD WITH A MINIMUM 6" CLEARANCE ON ALL SIDES.
6. ADEQUATE SUPPORT, EXCLUDING WATER LINES, SHALL BE PROVIDED UNDER ASSEMBLY VALVES FOR ASSEMBLIES THAT ARE 3 INCHES OR LARGER. ADJUSTABLE PIPE STAND SUPPORTS SHALL BE CONSTRUCTED OF MIN. 2" DIA. PIPE AND SHALL HAVE A FLOOR FLANGE FOR FASTENING STAND TO CONCRETE SLAB. PIPE STANDS SHALL BE FASTENED TO CONCRETE SLAB USING CONCRETE EXPANSION ANCHORS. FOR ASSEMBLIES THAT ARE 10" OR LARGER A THIRD PIPE STAND SUPPORT UNDER THE ASSEMBLY WILL BE REQUIRED.
7. INSTALLATION SHALL BE MADE IN STRICT ACCORDANCE WITH LOCAL UTILITY AND MANUFACTURER’S STANDARDS. CONTACT THE CITY OF FORT SMITH UTILITY DEPARTMENT AT 784-2282 ON ANY QUESTIONS.
8. WATER MUST BE DRAINED FROM THE ASSEMBLY UNTIL THE HEATER(S) HAVE AC POWER DURING COLD MONTHS.
9. THE LOWEST POINT OF THE ASSEMBLY OR RELIEF PORT SHALL BE AT LEAST 12 INCHES BUT NOT MORE THAN 30 INCHES ABOVE THE PAD OR HIGH WATER LEVEL, WHICHEVER IS HIGHEST.

10. ALL TEST COCKS SHALL BE IN PLACE WITH SHUT-OFF VALVES.
11. ELECTRICAL WIRING FOR HEATERS IN ABOVE GROUND ENCLOSURES MUST BE IN CONDUIT THROUGH THE CONCRETE PAD. UNDERGROUND CONDUIT MUST EXTEND BEYOND THE EDGE OF THE PAD IN THE DIRECTION OF THE POWER SOURCE A DISTANCE OF 4 FEET. A CORD OR ROPE MUST BE TIED FROM THE END OF THE CONDUIT TO GROUND LEVEL AND TIED TO A STAKE MARKING ITS LOCATION PRIOR TO BACKFILLING. ELECTRICAL OUTLETS MUST BE AFFIXED TO THE ENDS OF THE ENCLOSURE ABOVE THE ASSEMBLY.
12. ONE ENCLOSURE KEY MUST BE PROVIDED TO THE CITY UTILITY DEPARTMENT. KEY MAY BE MAILED OR PROVIDED AT TIME OF FINAL INSPECTION.
13. ENCLOSURE DOORS MUST BE EASY TO REMOVE AND REINSTALL WITHOUT BINDING.
14. IF INSTALLING THE ASSEMBLY IN AN ABOVE GROUND ENCLOSURE DIRECTLY OVER AN EXISTING VAULT, THE VAULT MUST BE FILLED AND COMPACTED PRIOR TO INSTALLING THE ENCLOSURE PAD.
15. AN ADEQUATE AND PERMANENT METHOD OF HANDLING RELIEF VENT DISCHARGE AND TEST WATER DISCHARGE SHALL BE PROVIDED. PIPE DISCHARGE TO OUTSIDE OF BUILDING.
16. CLEAR UNOBSTRUCTED SPACE FOR THE RELIEF VENT SHALL BE PROVIDED TO PREVENT THE VENT FROM BECOMING BLOCKED OR FLOODED.
17. THE ASSEMBLIES MUST BE INSTALLED HORIZONTALLY. RELIEF PORT VENTS MUST POINT DOWN.
19. AN AIR-GAP SEPARATION SHALL BE PROVIDED BETWEEN THE RELIEF VENT AND ATMOSPHERE. IF A DRAIN LINE IS USED THE FACTORY BOLT ON AIR GAP AND DRAINAGE ATTACHMENT ARE REQUIRED.
20. THE RELIEF VENT OPENING SHALL NOT BE REDUCED IN SIZE.
21. A 2" OS&Y BLOW-OFF VALVE MUST BE INSTALLED IN THE WATER LINE IMMEDIATELY AFTER THE ASSEMBLY TO ALLOW FOR FLUSHING. TWO THROUGH EIGHT INCH ASSEMBLIES SHALL HAVE A BLOW-OFF NOT LESS THAN 2 INCHES IN DIAMETER. ASSEMBLIES LARGER THAN 8 INCH SHALL HAVE A MINIMUM 4 INCH BLOW-OFF. BLOW-OFF SHALL BE PIPED TO DISCHARGE TO THE EXTERIOR ATMOSPHERE OF THE VALVE ENCLOSURE.

PROVIDE A MINIMUM OF 48" INCHES OF PIPING BETWEEN EXTERIOR OF ENCLOSURE AND BLOW-OFF VALVE TO PREVENT CONDUCTION OF FREEZING TEMPERATURE TO THE VALVE. PIPE TO OUTSIDE OF BUILDING.

22. OWNER SHALL BE RESPONSIBLE FOR ADEQUATELY SECURING THE VALVE ENCLOSURE, OS&Y WHEELS AND ACCESS PANELS AGAINST VANDALISM, TAMPERING, ETC.
23. UPON COMPLETION OF INSTALLATION, INSTALLER MUST CALL JOHN BEARD AT 479-784-2282 FOR A FINAL INSPECTION.